




# Electric road construction: Road infrastructure impacts and solutions

Damien Bateman  
TRL - Senior pavement engineer  
April 2017

# Agenda

- Introduction
- Conventional pavement design
- Existing E-road design methods
  - Advantages and disadvantages of each
- Key findings from FABRIC test sites
- Key findings from WP45
- Conclusions

- Project task aims to:
    - Identify the requirements for the construction of E-roads (inductive power transfer systems)
    - Determine how these will align with current road construction and maintenance procedures
    - Evaluate potential impacts on infrastructure and identify possible solutions
- 

# Conventional pavement design

- Design methodologies vary across Europe
  - Impact of integration of IPT systems to be similar
- E.g. UK flexible pavements
  - Long Life Pavements (LLPs)
  - Pavements designed to last 40+ years without requiring any major structural rehabilitation
- E-roads expected to provide similar structural performance

## E-road design


- E-roads should be designed and built to satisfy current standards for conventional pavements
- E.g. Bus routes in the UK, Italy, Germany, Netherlands, and South Korea
- However there is no defined construction methodology
  - IPT system specific

# E-road construction types

Four E-road construction methodologies identified from existing IPT systems:

1. Trench-based construction
2. Micro-trench based construction
3. Full lane-width construction
4. Prefabricated full lane-width construction

# 1. Trench-based construction



(a) In-situ construction



(b) Prefabricated system

# In-situ build construction (KAIST)



**(a) Trench excavation and placement of pipes**



**(b) 1<sup>st</sup> Concrete layer**



**(c) Power supply system**



**(d) 2<sup>nd</sup> Concrete layer**



**(e) Tack coat**



**(f) Surface course**



# Precast build construction (KAIST)



(a) Trench excavation and placement of pipes



(b) 1<sup>st</sup> Concrete layer



(c) Pre-cast system



(d) Placement of pre-cast system



(e) Concrete fill around system




(f) Tack coat and surface layer application

# 1. Trench-based construction

- Advantages
  - Relatively quick
  - Lower initial costs
  - Possible use of low temp. asphalt (LTA) and non-ferrous aggregates in surface layer
- Disadvantages
  - Introduction of concrete in fully flexible pavement
  - Thermal cracking / reflective cracking
  - Higher maintenance costs

## 2. Micro-trench based construction



E.g. Italian test site: Micro-trench excavation, placement of coils, and application of cold mix asphalt

## 2. Micro-trench based construction


### ■ Advantages

- Relatively quick and low initial costs
- Use of cold mix asphalt and non-ferrous aggregates in surface layer
- Minimal damage to existing structure
- Lower maintenance costs

### ■ Disadvantages

- Depth of coils limited to air gap allowance (~40-100mm)
- Coils susceptible to damage from traffic loads

### 3. Full lane-width construction




Option 1. In-situ build construction

Option 2. Precast build construction

### 3. Full lane-width construction

- Advantages
  - Single longitudinal joints at lane interface
  - Likely lower whole life costs than trench construction
  - Factory construction quality (IPT systems built off-site)
  - Concrete protects IPT from effects of paving process (high temp. and compaction)
- Disadvantages
  - Slower construction
  - Requires 2 lane closures
  - Relatively high vehicle movements
  - Potential maintenance issues with transverse joints affecting the adjacent lanes

# 4. Full lane-width precast construction



## Precast build construction



E.g. Installation of Modieslab precast section

## 4. Full lane-width precast construction

### Advantages:

- Relatively quick installation
- Factory construction quality
- Single longitudinal joint(s) at lane interface(s)
- Lower whole life costs



## 4. Full lane-width precast construction

### Disadvantages:

- High initial cost
- Requires two lanes of traffic management
- Joint maintenance
- Potential maintenance issues with transverse joints affecting the adjacent lanes
- Potential disruption to road users due to transport of systems to site
- Precast slabs prone to movement under traffic loading

# Agenda

- Introduction
- Conventional pavement design
- Existing E-road design methods
  - Advantages and disadvantages of each
- Key findings from FABRIC test sites
- Key findings from WP45
- Conclusions

# Key findings from FABRIC test sites

## POLITO results

- Limited knowledge gained on the structural performance of IPT systems in existing roads
- Embedding the coil in concrete resulted in high capacitive coupling between the coil and concrete
  - At high frequencies close to the working frequency of the system
- Solution – insertion of a non-conductive material acting as a dielectric between the coil and ground
- Micro-trench based approach was relatively quick to complete
- Use of cold mix asphalt worked well with IPT equipment

# Key findings from WP45

## Laboratory testing (KTH)


- Significant failure at the interface when subjected to cyclic tension-compression testing
  - More rapid failure of E-road samples



# Key findings from WP45 (Cont'd)

## Laboratory testing (KTH)

- Higher deformations at the asphalt/concrete interfaces and the corners
- Significant increase of voids



X-ray scanning images before and after 10,000 cycles of dynamic loading

# Key findings from WP45 (Cont'd)

## Finite Element Analysis results (POLITO and KTH)

- Overlay thickness had a greater effect to the overall structural integrity of E-road in comparison to material stiffness
- The use of joint materials (SAMI, geo-grid, etc.) reduced the level of stress/strain at the base of the asphalt layer
- The bonding at the asphalt/CU interface is critical to E-road structural integrity
  - Especially under braking forces

# Conclusions

- Existing E-roads (Europe and South Korea) demonstrate various construction methods
- No defined construction methodology
  - IPT system specific

# Conclusions (Cont'd)

- Conventional road materials should be suitable for use in E-roads
  - LTAs and non-ferrous aggregates should be considered in surface layer (if required)
  - Use of non-conductive materials as a dielectric between the coil and road materials



## Conclusions (Cont'd)

- Limited knowledge of structural performance of E-roads
- Laboratory testing and theoretical simulations suggest that:
  - Concerns of premature failure at the interface
  - The use of joint materials at the interface may reduce the levels of stress/strain
  - Good bonding at the interface is critical to structural integrity

Thank you!

Questions?

